Schedule.

Items of work	Unit	Quantity	Rate
1. Earthwork excavation for founds and for forming bank in gravelly soil mixed with stones including lead and lift.	1,000 C.ft.	16,000 C,ft.	
2. Concrete broken stone in mortar ...	100 ,,	1,200 ,,	
3. Size stone in mortar	100 ,,	800 ,,	
4. Plastering with cement	100 S.ft.	400 S.ft.	
5. Rough stone revetment with 6" jelly backing ...	100 C.ft.	3,800 C.ft.	
6. Do with old stones	100 ,,	2,784 ,,	
7. Dismantling old revetment	100 ,,	2,784 ,,	
8. Rough stone dry for flooring and apron ...	100 ,,	3,820 ,,	
9. Clearing thick bushy jungle ...	...	..	
10. Putting gravel behind the revetment watering and tamping including B. T. charges for bringing gravel to the site.	1,000 C.ft.	5,000 C.ft,	
11. Turfing earth slope including watering till it takes root.	S.yd.	178 S.yd.	

V. RAMANUJALU NAIDU,
Executive Engineer.

MYSORE RAILWAYS, MYSORE.

MYSORE DIVISION (OPEN LINES).

Notification dated 11th July 1929.

Notice is hereby given that sealed tenders will be received by the Executive Engineer, Open Line Division, Mysore Railways, Mysore, any day up to 2 P.M. of Monday the 5th August 1929, from contractors who are willing to undertake the "Widening of the Railway overbridge on the Yelwal Road at mile 294—19-20 on Mysore-Nanjangud Section."

2. Every tender should be accompanied by an earnest money of Rs. 100 which can be paid either in currency notes to the Executive Engineer, Mysore Railways, Mysore, along with the tender or can be paid to the Auditor, Mysore Railways, Mysore, and the receipt thereof enclosed along with the tender. Such of the tenderers who pay the amount to the Auditor should advice him that the amount is paid on account of a tender for "Widening the Railway overbridge on the Yelwal Road at mile 294—19-20 on Mysore-Nanjangud Section."

(*a*) Tender should be submitted in special forms which can be obtained from the Executive Engineer, Mysore Railways, Mysore, on payment of rupee one.

3. The earnest money of the unsuccessful tenderers will be returned as soon as possible after the tenders are disposed of.

4. Tenders which are not accompanied with the earnest money specified in para 2, will not be considered.

5. The successful tenderer should execute within a week from the date of notification of acceptance of his tender, the usual Railway Schedule Agreement. Failure to comply with this condition will render the tenderer liable for forfeiture of the earnest money.

6. The name of the accepted tenderer will be posted on the Notice Board of the Executive Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will be replied.

7. The final acceptance of the tender will rest with the Engineer-in Chief, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself the right to reject, without assigning any reasons therefor, any or all the tenders.

8. Work should be started within a week from the date of acceptance of tender and a uniform monthly rate of progress should be guaranteed. The work agreed on should be completed in five months from date of starting. The accompanying schedule gives the approximate quantity of works and this quantity is not guaranteed.

9. The time limit specified in para 8 should be strictly adhered to and any violation of this will render the contractor liable for forfeit his 5 per cent deposit amount under Clause No. 10 of the Schedule Agreement, not as a penalty but as ascertained and liquidated damages recoverable accordingly.

10. Plans and specifications and other details of work to be done are available for inspection in the Executive Engineer's Office, Mysore Railways, Mysore, where intending [illegible] obtain required information during office hours.

11. In all matters of dispute regarding rates, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Engineer-in-Chief, will be final and legally binding.

Schedule.

	Description of work	Unit	Quantity
1	Earthwork excavation in all soils	1,000 C.ft.	3,129
2	Concrete in mortar	100	639
3	Size stone in mortar	C.ft.	4,776
4	Chunam pointing	Sqr.	1,556
5	Ashlar coping 6" thick dressed and champhered	S.ft.	144
6	Ashlar coping 4" thick	,,	102
7	Kerbstone 4" thick including dressing and fixing	R.ft.	150
8	Dismantling the existing parapet wall	100 C.ft.	562
9	Dismantling and resetting coping slabs	S.ft.	100
10	Rivetting and fixing steel trough 28·78 lbs. per Sq.ft. for the extension only (troughs to be supplied departmentally).	Cwt.	79
11	Removing and refixing the existing plate parapet	L. S.	...
12	Forming road and foot-path	L. S.	...
13	Painting trough, etc.	L. S.	...
14	Clearing site and levelling ground	L. S.	...

M. RAMAIYA,
Executive Engineer,

KADUR DIVISION.

Dated 1st July 1929.

1. Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 1st August 1929, for closing the leak in the Madag tank bund, Kadur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. to 5 P.M. on (office days).

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for closing the leak in the Madag tank bund, Kadur Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantities for closing the leak in the Madag tank bund Kadur Taluk.

No.	Items of work	Per	Quantity	Rate	
				In figures	In words
1	Earthwork excavation in the centre of bund ordinary soil.	C.yd.	3,094		
2	Filling the trench with good jelly for jelly drain	,,	288		
3	Plugging the holes with puddle ...	,,	100		
4	Earth filling in the trench including watering and tamping in layers.	,,	2,760		
5	Rough stone revetment with jelly backing ...	,,	74		
6	Removing the revetment in front and resetting after examining the leaks.	,,	340		
7	Jungle clearing with roots	Lump sum			
8	Gravel backing to revetment in front 12" thick	C.yd.	113		